



Member of the MacTaggart Scott Group

**MACSCOTT BOND LTD**

**Aberdeen Division**

UNIT 2, BLACKNESS ROAD  
ALTENS INDUSTRIAL ESTATE

ABERDEEN AB12 3LH

Tel: 01224 873113 Fax: 01224 877700

Engineering with Hydraulics

ISO 9001 CERTIFIED ORGANISATION



United Register of Systems Cert No. 97120



**OPERATING INSTRUCTIONS FOR MSB 251**

**DUAL SYSTEM HYDRAULIC PRESSURE TEST UNIT WITH ACCUMULATION**

**Prior to use of this Equipment, these instructions should be Read , Understood and its Operation Carried out by Designated “Competent “ Personnel**

ITEM NO:	INSTRUCTIONS :
1.	<b>Fill tank by connecting to “Tank Fill Line”. Ensure that the Three Way Ball</b>
	<b>Valve handle is vertical.</b>
2.	<b>Operate Circulation Pump to fill.</b>
3..	<b>Shut off Circulating Pump.</b>
4.	<b>Move the Three Way Ball Valve to horizontal</b>
5.	<b>Operate Circulating Pump to clean fluid</b>
6.	<b>Ensure Valves V1 to V7 are closed</b>
7.	<b>To operate M.P. system open V6</b>
	<b>To operated H.P. System open V1</b>
8.	<b>To release M.P. System open V3</b>
	<b>To release M.P. System open V2</b>
9.	<b>To release M.P Pump on H.P. System open V5</b>

**NOTE :** Customers are advised to flush the Unit through with their own system fluid in order to eliminate the danger of system contamination due to unforeseen circumstances and / or in the event of wrongly supplied fluid relating to fluid type.